



MSBA Amherst-Pelham Regional MS
Roof Replacement
 Amherst, MA

8/20/2025

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Cost
TRADE COSTS				
Roof Replacement Option A	Jul-26	104,418	\$49.99	\$5,219,872
HazMat removals allowance				\$920,640
SUBTOTAL TRADE COSTS	Jul-26			\$6,140,512
Design and Estimating Contingency		10.0%		\$614,051
Escalation to Bid		5.3%		\$325,447
SUBTOTAL				\$7,080,010
Subcontractor Bonds				In rates
General Conditions	8.0%			\$566,401
General Requirements	2.0%			\$141,600
Winter Conditions				excl
Insurances - GLI/Builders Risk	1.40%			\$99,120
Bond	0.70%			\$49,560
Building Permit				Waived
Overhead & Profit	5.0%			\$354,001
TOTAL ESTIMATED CONSTRUCTION COST		104,418	\$79	\$8,290,692

Alternates (Markedup) :

OPTA Pitch towards roof edge w/ (2) new roof drains	ADD	BASE
OPTB New roof system w/ extg roof drains in place	DEDUCT	\$ (65,744)
OPTC Remove existing adhered membrane and adhere new felt back membrane in low rise foam felt back adhesive. Repair any damage insulation in the process (assumes new edge conditions)	DEDUCT	\$ (3,485,091)
OPTD Remove existing adhered membrane and install a new membrane in its place. Repair any damage insulation in the process and add additional ½" HD. (assumes new edge conditions)	DEDUCT	\$ (3,700,766)
OPTE Leave the existing adhered membrane and install a new Sikalastic RoofPro or RoofCoat recover system with a 25 or 30 year warranty over top. Repair any damage insulation in the process.(credits back entirety of roof scope, no new edges, accessories, flashings, MEP disconnect/reinstall)	DEDUCT	\$ (3,728,628)



CONSTRUCTION COST SUMMARY IN CSI FORMAT

Roof Option A

DIVISION

Subtotal

Total

DIV. 2 EXISTING CONDITIONS

024100 Demolition

DIV. 4 MASONRY

\$146,300

042000 Unit Masonry

\$146,300

DIV. 6 WOODS & PLASTICS

\$172,392

061000 Rough Carpentry

\$172,392

062000 Finish Carpentry

DIV. 7 THERMAL & MOISTURE PROTECTION

\$4,547,625

074000 Roofing & Siding Panels

075000 Membrane Roofing

\$4,297,587

076000 Flashing & Sheet Metal

077000 Roof & Wall Specialties / Accessories

\$145,620

079200 Joint Sealants

\$104,418

DIV. 9 FINISHES

\$2,040

092100 Gypsum Board Assemblies

095100 Acoustical Ceilings

\$2,040

DIV. 21 FIRE PROTECTION

210000 Fire Protection

DIV. 22 PLUMBING

\$103,040

220000 Plumbing

\$103,040

DIV. 23 HVAC

\$183,425

230000 HVAC

\$183,425

DIV. 26 ELECTRICAL

\$65,050

260000 Electrical

\$65,050

SUBTOTAL DIRECT (TRADE) COST

Building

\$5,219,872



CODE	DESCRIPTION	QTY	UNIT	UNIT COST	COST	SUBTOTAL COST	TOTAL COST
------	-------------	-----	------	-----------	------	---------------	------------

Roof Option A

02 EXISTING CONDITIONS

024100 Demolition

Demolition by Div 07

SUBTOTAL:

\$ -

TOTAL, DIVISION 2 - EXISTING CONDITIONS

04 MASONRY

042000 Unit Masonry

Roof to wall detail @ extg brick, allow remove & reinstall brick
for wall flashings

357 lf

400.00

142,800

Brick infill at louver

1 ls

3,500.00

3,500

SUBTOTAL:

\$ 146,300

TOTAL, DIVISION 4 - MASONRY

\$146,300

05 METALS

Metal Fabrications

Misc. metals as req'd at roof, allowance

104,418

-

SUBTOTAL:

\$ -

TOTAL, DIVISION 5 - METALS

06 WOOD & PLASTICS

061000 Rough Carpentry

3/4" exterior plywood sheathing on 16 GA furring channels
A1.2/11

456 sf

12.00

5,472

3/4" exterior plywood sheathing on 16 GA furring channels
A1.2/12

921 sf

12.00

11,052

Wood blocking @ roof edges

25,978 lf

6.00

155,868

SUBTOTAL:

\$ 172,392

062000 Finish Carpentry

No items in this section

-

SUBTOTAL:

\$ -

TOTAL, DIVISION 6 - WOOD & PLASTICS

\$172,392

07 THERMAL & MOISTURE PROTECTION

075000 Membrane Roofing

Roof Qty Summary

-

Roof 1 Area

104,418 sf

-

-

Roof Demolition

R&D roofing & insulation in all flat roofs to deck

104,418 sf

5.00

522,090

R&D all walkmats

sf

w/ roof demo above

R&D extg drip edge at built up roof edges

lf

w/ roof demo above

R&D roof drain, including leader, bowl & basket cover

ea

w/ plumbing

R&D extg boiler room masonry chimney to below roof deck

1 ls

6,500.00

6,500

R&D extg antenna, extend base & reinstall

1 ls

2,500.00

2,500

-

New Roof

-

Roofing, membrane

104,418 sf

32.00



CODE	DESCRIPTION	QTY	UNIT	UNIT COST	COST	SUBTOTAL COST	TOTAL COST
Roof Option A							
61	OPTA PVC Membrane 80mil	104,418	sf	16.00	1,670,688		
62	OPTA 1/2" Coverboard	104,418	sf	3.00	313,254		
63	OPTA Rigid insulation 5"	104,418	sf	7.50	783,135		
64	OPTA Tapered insulation, minimum 3", allow	5,221	sf	5.25	27,410		
65	OPTA AVB	104,418	sf	2.50	261,045		
66	OPTA Gyp Sheathing	104,418	sf	3.00	313,254		
67	Walkway pad, allowance not drawn	3,133	sf	14.00	43,862		
68	OPTB Keep pitch as is towards extg roof drain	104,418	sf		Alternate w/ plumbing		
69	OPTC Adhere new felt back membrane in low rise foam felt back adhesive. Repair any damaged insulation	104,418	sf	20.40	Alternate		
70	OPTD Install a new membrane in its place. Repair any damage insulation in the process and add additional 1/2" HD	104,418	sf	18.87	Alternate		
71	OPTE Leave the existing adhered membrane and install a new Sikalastic RoofPro or RoofCoat recover system with a 30 year warranty over top. Repair any damage insulation in the process.	104,418	sf	31.40	Alternate		
72							
73	<u>Roof Edges & flashings</u>						
74	Roof edge fascia & flashing drip edge system				-		
75	Fascia A-1.2/01 (PVC clad head welded fascia w/ cont cleat, caulk jt, break metal trim)	355	lf	50.00	17,750		
76	Rake A-1.2/02 (PVC clad head welded fascia w/ cont cleat, caulk jt, break metal trim)	330	lf	50.00	16,500		
77	Fascia A-1.2/03 (PVC clad head welded fascia w/ cont cleat, caulk jt, break metal trim) w/ gutter in accessories	245	lf	50.00	12,250		
78	Fascia A-1.2/04 (PVC clad head welded fascia w/ cont cleat, caulk jt, break metal trim) w/ gutter in accessories	201	lf	50.00	10,050		
79	Fascia A-1.2/05 (PVC clad head welded fascia w/ cont cleat, caulk jt, break metal trim) w/ gutter in accessories	57	lf	50.00	2,850		
80	Fascia A-1.2/06 (PVC clad head welded fascia w/ cont cleat, caulk jt, break metal trim) w/ gutter in accessories	47	lf	50.00	2,350		
81	Fascia A-1.2/09 (PVC clad head welded fascia w/ cont cleat, caulk jt, break metal trim) w/ gutter in accessories	1,134	lf	50.00	56,700		
82	Fascia A-1.2/10 (PVC clad head welded fascia w/ cont cleat, caulk jt, break metal trim) w/ gutter in accessories	251	lf	50.00	12,550		
83	Fascia A-1.2/11 (PVC clad head welded fascia w/ cont cleat, caulk jt, break metal trim) w/ gutter in accessories	152	lf	50.00	7,600		
84	Fascia A-1.2/12 (PVC clad head welded fascia w/ cont cleat, caulk jt, break metal trim)	307	lf	50.00	15,350		
85	Fascia A-1.2/13 (PVC clad head welded fascia w/ cont cleat, caulk jt, break metal trim)	252	lf	50.00	12,600		
86	Roof to wall flashing system, membrane						
87	Roof to wall flashing / expansion jt A-1.2/11	152	lf	65.00	9,880		
88	Roof to wall flashing detail A-1.2/12	307	lf	30.00	9,210		
89	Fascia/roof to wall A-1.3/12 @ ladder	25	lf		included		
90	Roof to wall flashing system, masonry						
91	Roof to wall flashing detail A1.3/11 (thru wall flashing assembly, brick by masonry)	357	lf	60.00	21,420		
92	Louver infill A-1.2/07,08 (thru wall flashing assembly, brick by masonry)	19	lf	60.00	1,140		
93	Expansion joint system						
94	Roof expansion jt detail A1.3/01	392	lf	65.00	25,480		
95	Corra-lock concealed fastener metal panel or equal on furring channels A-1.2/13	756	sf	60.00	45,360		
96	Miscellaneous flashings, allowance	104,418	sf	0.50	52,209		
97							
98	<u>Roof Component flashings</u>						
99	Roof component, exhaust fan A1.3/08	19	ea	200.00	3,800		
100	Roof component, gooseneck curb A1.3/09	3	ea	200.00	600		
101	Roof component, duct curb/penetration A1.2/14	40	ea	200.00	8,000		
102	Roof component, pitch pocket A1.3/04	5	ea	200.00	1,000		
103	Roof component, vent stack A1.3/03	35	ea	100.00	3,500		
104	Roof component, hot stack flue A1.3/10	1	ea	100.00	100		
105	Roof component, RD A1.3/02	17	ea	200.00	3,400		
106	Roof component, roof hatch A1.3/07	5	ea	400.00	2,000		
107	Roof component, antenna base A1.3/06	1	ea	200.00	200		



CODE	DESCRIPTION	QTY	UNIT	UNIT COST	COST	SUBTOTAL COST	TOTAL COST
------	-------------	-----	------	-----------	------	---------------	------------

Roof Option A

108 075000 SUBTOTAL: \$ 4,297,587

109

077000 Roof & Wall Specialties / Accessories

111

112 Gutter 2,087 lf 35.00 73,045

113 Downspout 625 lf 35.00 21,875

114 New guard rail @ roof hatches 125 lf 200.00 25,000

115 New roof ladder, exterior 2 ea 3,500.00 7,000

116 New roof ladder, interior 5 ea 3,500.00 17,500

117 Roof accessory, guy wire anchor A1.3/05 4 ea 300.00 1,200

118 077000 SUBTOTAL: \$ 145,620

119

079200 Joint Sealants

121 Joint sealants as req'd @ roof 104,418 sf 1.00 104,418

123 079200 SUBTOTAL: \$ 104,418

124

125

TOTAL, DIVISION 7 - THERMAL AND MOISTURE PROTECTION \$4,547,625

127

09 FINISHES

129

095100 Acoustical Ceilings

131

132 Remove & reinstall ACT ceiling @ roof drain 136 sf 15.00 2,040

133 095100 SUBTOTAL: \$ 2,040

134

TOTAL, DIVISION 9 - FINISHES \$2,040

136

22 PLUMBING

137

138

220000 Plumbing

140

Plumbing Demolition

142 Plumbing demolition, disconnect, existing roof drains & cap for reconnection 34 ea 485.00 16,490

143 Plumbing demolition, cut back existing VTR's & cap for 42 ea 255.00 10,710

144 Plumbing demolition, remove metal chimney & cap 1 ea 275.00 275

Plumbing

146 Install extg roof drains - tie to existing 32 ea 800.00 25,600

147 Install new roof drains, sump, adjustable extension, insulation - tie to existing 2 ea 1,800.00 3,600

148 VTR, Extend piping 18" above new roof and reconnect 42 ea 305.00 12,810

149 New double wall stainless chimney, extend 20', roof cap & rain hood 1 ea 1,460.00 1,460

150 Connect downspout into extg drainage 250 lf 100.00 25,000

151 Plumbing

152 Project supervision, coordination, permits & fees 1 ls 7,094.50 7,095

153 220000 SUBTOTAL \$ 103,040

154

TOTAL, DIVISION 22 \$103,040

156

23 HVAC

157

158

230000 HVAC

160

HVAC Demolition

162 Disconnect & remove exhaust fans 38 ea 790.00 30,020

163 Disconnect & remove air cooled condenser(s), reclaim refrigerant, cut & cap refrigerant piping 2 ea 2,040.00 4,080

164 Disconnect & remove wall louver & cap ductwork 2 ea 660.00 1,320

165 Disconnect & remove gooseneck & cap ductwork 1 ea 560.00 560

166 HVAC

167 Provide & install new exhaust fans w/ curb, backdraft damper & controls 38 ea 2,500.00 95,000



CODE	DESCRIPTION	QTY	UNIT	UNIT COST	COST	SUBTOTAL COST	TOTAL COST
Roof Option A							
168	Reinstall air cooled condenser, new sleepers, reconnect all piping, insulate & test system	1	ea	3,390.00	3,390		
169	New roof goosenecks, reconnect to existing ductwork	9	ea	1,620.00	14,580		
170	<u>HVAC Miscellaneous</u>						
171	Rigging, hoisting, setting	1	ls	12,000.00	12,000		
172	Test, balance, commissioning of systems, start up	1	ls	5,800.00	5,800		
173	Project supervision, coordination, permits & fees	1	ls	16,675.00	16,675		
174 230000	SUBTOTAL					\$	183,425
175							
176	TOTAL, DIVISION 23						\$183,425
177							
178	26 ELECTRICAL						
179							
180							
181	260000 Electrical						
182							
183	<u>Gear and Distribution</u>						
184	Modify and make connections at existing panelboards	1	ls	2,500.00	2,500		
185							
186	<u>Equipment Wiring</u>						
187	Disconnect exhaust fans	38	ea	350.00	13,300		
188	Disconnect air cooled condenser	2	ea	350.00	700		
189	New Exhaust fan, allow for feed and connection	38	ea	850.00	32,300		
190	Air cooled condenser, allow for feed and connection	1	ea	2,000.00	2,000		
191	30A disconnect switch WP	1	ea	850.00	850		
192	Light, switch WP, GFI WP and circuitry	1	ea	1,000.00	1,000		
193	F&I new cabling to Weather Station (Weather Station provided by others)	1	ls	1,000.00	1,000		
194	F&I new wiring to Weather Station (New Antenna provided by others)	1	ls	1,000.00	1,000		
195	New Weather Station				By others		
196	New Antenna				By others		
197	SUBTOTAL						
198							
199	<u>Miscellaneous</u>				-		
200	Allow for modifications to Lightning terminals	1	ls	5,000.00	5,000		
201	Remove and reinstall lighting and any LV device (allow)	1	ls	1,000.00	1,000		
202	Minimal demolition work	1	ls	1,000.00	1,000		
203	Coordination, BIM	1	ls	2,000.00	2,000		
204	Permit and fees	1	ls	1,400.00	1,400		
205 260000	SUBTOTAL					\$	65,050
206							
207	TOTAL, DIVISION 26						\$65,050
208							